

To: 1 031063  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,780  
NE SE NW, SEC. 27, T 34 S, R 20 W  
3380 feet from S section line  
3180 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4145  
Operator: Roberts & Murphy, Inc.  
Name & Address: P.O. Box 7125  
Shreveport, LA 71119

Lease Name Baker Well # 1-27  
County Comanche 212.88  
Well Total Depth 6550 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 655

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Tri-Ad Drilling License Number 7345

Address 5400 North Grand Blvd., Oklahoma City, OK 73112

Company to plug at: Hour: 2 p.m. Day: 18 Month: 2 Year: 19 90

Plugging proposal received from Lee Jenkinson

(company name) Tri-Ad Drilling (phone) 405-948-6006

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1150' with 50 sx cement, 2nd plug at 660' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7 p.m. Day: 18 Month: 2 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1150' with 50 sx cement,

2nd plug at 660' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

STATE CORP. (if additional description is necessary, use BACK of this form.)

INVOICE D-1990  
DATE 3-2-90 2-27-1990

Signed Steve Durrant (TECHNICIAN)

DATE 3-2-90  
INV. NO. 27593