

8-9

4-060338

TQ:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-195-22,112 ⁰⁰⁻⁰⁰

W2 NW SE /4 SEC. 10, 12 S, 24 W
1980 feet from S section line
2310 feet from E section line

Operator license# 9482

Lease Wolff well # 1

Operator: National Petroleum Reserves

County Trego

Address: 250 N. Rock Road
#340
Wichita, Kansas 67206

Well total depth 4430 feet ^{143.97}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 216 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: Russell, Kansas 67665

Company to plug at: Hour: 7:45P.M. Day: 9 Month: August Year: 92

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations Phone: 913-483-3518

Were: Order 190 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per sx.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 7:45P.M., Day: 9, Month: August, Year: 92

Actual plugging report:
1st. plug at 2075' w/25 sxs. - Anhydrite 2048' - 2091'.
2nd. plug at 1150' w/100 sxs. - Dakota 837' - 1137'.
3rd. plug at 270' w/40 sxs. - Surface pipe to 216'.
4th. plug at 40' w/10 sxs.
15 sxs. in Rathole.

Remarks: Halliburton Cementing.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO

Plugged through TUBING , CASING . Elevation: 2487

RECEIVED
STATE CORPORATION COMMISSION
09-24-1992
CONSERVATION DIVISION
Wichita, Kansas

I did INVOICED did not [X] observe the plugging.

DATE 9-24-92
WV. NO. 36251

Handwritten signature

(agent)