

4-050146

9-29

20  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-179-21,045 -0000

SW NE SW /4 SEC. 16, 10 S, 26 W  
1650 feet from S section line  
3560 feet from E section line

Operator license# 3680

Lease Tilton well #16-11

Operator: L.B. Industries, Inc.

County Sheridan

Address: 12200 E. Briarwood Ave  
Suite 250 (303)790-8340  
Englewood, Colorado 80112

Well total depth 4440 feet  
Conductor Pipe: \_\_\_\_\_ inch @ \_\_\_\_\_ feet  
Surface pipe 8 5/8 inch @ 326 feet

144.30

Aband. oil well \_\_\_\_\_, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A X

Plugging contractor: Chief Drilling Inc. License# \_\_\_\_\_

Address: \_\_\_\_\_

Company to plug at: Hour: PM Day: 29 Month: September Year: 1992

Plugging proposal received from: Harold Dinkel

Company: Chief Drilling Inc. phone: \_\_\_\_\_

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ <u>2230</u> feet with	25	sacks	Rat hole: <u>15</u> sacks
2nd plug @ <u>1310</u> feet "	100	"	Mouse hole: <u>10</u> sacks
3rd plug @ <u>375</u> feet "	40	"	
4th plug @ <u>40</u> feet "	10	"	with 8 5/8" wiper plug

Plugging Proposal Received by: Marvin L. Miller

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 11:15 PM, Day: 29, Month: September, Year: 1992

Actual plugging report: Hole reported plugged as above.  
Order 200 sx 60/40 pozmix w/ 6% gel and 1/4# celloflake or flowcel per sk

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Elevation: 2586, Anhydrite: 2206-2266 feet, Anhydrite plug: 2230  
Bottom plug (in place): Yes X, Calc \_\_\_\_\_, No \_\_\_\_\_ Arbuckle: None

10-8-92  
OCT 8 1992

Did Not penetrate Arbuckle, cemented by Halliburton Services

CONSERVATION DIVISION  
Wichita, Kansas

I did NOT observe the plugging. Marvin L. Miller

DATE 10-20-92

Marvin L. Miller P.I.R.T.II  
(agent)

WML NO. 36505