

To: 6 031306  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Operator: Chief Drilling Co. Inc.

Name & Address 224 East Douglas #350

Wichita, Ks. 67202

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cement Co. License Number \_\_\_\_\_

Address Russell, Ks.

Company to plug at: Hour: PM Day: 14 Month: Dec Year: 19 89

Plugging proposal received from Gary Lindenmuth

(company name) Chief (phone) \_\_\_\_\_

were: 8 5/8" set at 258' w/160 sks cwc. 4 1/2" set at 4122' w/150 sks.

Perfs at 3870' - 4034'. Port collar at 2236'. Shot at 2000' and 1350'. Order 250 sks

65/35 poz 10% gel 2% dicel 500# hulls. Allied Cement Co. Newman Water Trucks.

Plugging Proposal Received by \_\_\_\_\_

Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2:00 PM Day: 14 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Squeezed 4 1/2" casing w/130 sks cement blend w/

400# hulls. Mixed into max psi 1400#. Close in psi 800#. Squeezed 8 5/8" w/100 sks

cement blend to max psi 200#. Close in psi 200#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

1-17-90  
JAN 17 1990

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form)  
CONSERVATION DIVISION  
Wichita, Kansas

I (did / ~~did not~~) observe this plugging.

INVOICED

DATE JAN 24 1990

WV. NO. 27109

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow