

4-031828

6-10

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-20,593-0000

E2 NW SE /4 SEC. 16, 10 S, 23²⁶ W
1980 feet from S section line
1650 feet from E section line

Operator license # 31142 Lease Martin well # 3

Operator: Petroleum Property Services County Sheridan

Address: 155 N. Market Well total depth 4075 feet 132.43
Suite 1010 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 244 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Kelso Casing Pulling License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 10 Month: June Year: 93

Plugging proposal received from: Dave and Dennis Hamel K.C.C.

Company: Kelso Casing Pulling Phone:

Were: Order 250 sx. 65/35 pozmix - 10% gel. - 300# hulls.
Common cement and sand.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:30 P.M., Day: 10, Month: June, Year: 93

Actual plugging report: 8 5/8" set @ 244' w/175 sx. cwc. 4 1/2" set @ 4037' w/150 sx. PBTD 4009'. Perf. 3861' - 3905'. Sanded bottom to 3800' w/4 sx. common cement on sand with bailer. Shot @ 2250'. Anhy. 1650' - 1350' and recovered 1004'. Mix & pump 35 sx. cement blend from 1650' to 2250'. Mix and pump 65 sx. 1000' to 1650' w/400# P.S.I. Shot off @ 1004'. Laid down rack and skid. Mix & Pump 63 sx. to circulate with Max. P.S.I. 500#. Laid down casing top off with 15 sx. cement blend. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO
Plugged through TUBING, CASING. Elevation: GL

RECEIVED
CORPORATION COMMISS
7-14-93
JUL 14 1993

I did [X] / did not [] observe the plugging.

Carl Goodrow

BAH (agent) CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 7-19-93
INV. NO. 38146