

To: 6 070892
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,539 -0000

SE SW NWSEC. 1, T 10 S, R 31 W/EX

2970 feet from S section line

4290 feet from E section line

Lease Name Huelsmann Well # 1-1

County Thomas 150.80

Well Total Depth 4640 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 259

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Operator: Chief Drilling Inc.

Name & Address 224 E. Douglas #530

Wichita, Ks. 67202

Douglas W. Thimesch

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Chief Drilling Inc. License Number 5886

Address Wichita, Ks. 67202

Company to plug at: Hour: AM Day: 17 Month: Dec. Year: 19 90

Plugging proposal received from Marion Burris

(company name) Chief Drilling Inc (phone)

were: 8 5/8 259 ft. s.p. cwc w/160 sks 60/40 poz 2% gel 3% cc. By Allied.

Miss. well. Elv. 2994. Anhy 2566. No circ. problems. Mud cond. 43 vis. 9.5 weight

8.8 water loss. Proposal 200 sks 60/40 poz 6% gel 3% cc. Spot with drill stem

(circulate) Spot heavy mud between all plugs. 25 sks at 2580. 100 sks w/ 1 sk

f.c. at 1690. 40 sks at 400. 10 sks at 40. 15 sks in rathole, Circ. 10 sks
mousehoe, circ.

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN) *MJS*

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 5:30PM Day: 17 Month: Dec. Year: 19 90

ACTUAL PLUGGING REPORT Chief ordered 200 sks 60/40 poz 6% gel 3% ca cl. Circ hole.

Spotted cement through drill stem, heavy mud between all plugs.

1st plug at 2580 ft. w/25 sks cement.

2nd plug at 1690 ft. w/100 sks cement w/ 1 sk f.c.

3rd plug at 300 ft. w/40 sks cement.

4th plug at 40 ft. w/10 sks cement

15 sks in rathole (circ) 10 sks in mousehole, Cir.

12-28-90

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-8-91

INV. NO. 30408

Gibbs

Signed Marion J. Schmidt
(TECHNICIAN)