

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656

Operator: Davis Petroleum Inc.

Name & Address Route 1 Box 183 B

Great Bend, Ks. 67530

Abandoned Oil Well ^X _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635 CP

Address Box 768 Great Bend, KM.

Company to plug at: Hour: PM Day: 4 Month: August Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing (phone) _____

were: 8 5/8" set at 276' w/125 sks cwc 4 1/2" set at 4553' w/125 sks.

PBTD 4550¹. Perf 4367¹ - 4377¹. Order sand and common cement. Pull pipe. Order 225 sks

65/35 poz 10% gel 500# hulls. Allied Cement Co. Hensley Water Truck.

Plugging Proposal Received by Carl Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 1:45PM Day: 4 Month: August Year: 19 89

ACTUAL PLUGGING REPORT Sand bottom to 4300' w/4 sks common cement on sand w/bailer

~~Shots at 2600 and 1900 and 1337. Recovered 1337 of casing. Squeezed 8 5/8" casing w/225 sks cement blend w/500#Hulls mixed in to max psi 500#. Close in psi 150#. Plug~~

complete.

RECEIVED
STATE CORPORATION COMMISSION

AUG 14 1989

Remarks:

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this form.)

1 (did ~~not~~) observe this plugging.

DATE 8-17-89

WV. NO. 25656

Signed

Carl Goodrow

FORM CP-2/3
Rev. 01-84