

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-21, 223-00 00

SW-SW-NE, Sec. 2, T 12 S, R 25 W/E
2340 feet from N section line

2340 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6509

Lease Name LACERTE Well # 1

Operator: CLA-MAR OIL, INC.
Name & Address: 2705 VINE #8
HAYS, Mo. 67601

County TREGO

Well Total Depth 4535 feet \$147.39

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 228

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor HEBERG DRILLING License Number 5669

Address Box 32 MORLAND, MO. 67650

Company to plug at: Hour: 12:00 PM Day: 2ND Month: JUNE Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO JERRY HELBURG

(company name) HEBERG DRILLING (phone) 913-628-8150 PM

were: 8 5/8" - 228 FT SP CUL^W / 135ST COMMON 2% GEL-3% CA-CL (ALLIED)

ORDER 185ST 50/50 FORMIX 6% GEL-3% CA-CL AND 8 5/8" PLUG

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

NO AIRBUCKLE - ELV. 2295 - ANH. 2245.

Signed [Signature]
(TECHNICIAN) (DOIC)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00 PM Day: 2ND Month: JUNE Year: 19 83

ACTUAL PLUGGING REPORT

8 5/8" - 228 FT SP. CUL^W / 135ST COMMON 2% GEL-3% CA-CL (ALLIED)

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

1ST PLUG @ 2280 FT^W / 25ST CNT., 2ND PLUG @ 960 FT^W / 100 CNT.

3RD PLUG @ 240 FT^W / 40ST CNT., 4TH PLUG SOLID BRINE @ 40ST CNT.

10ST CNT IN RAT CABLE (CIRCULATE) CNT. BY ALLIED CNT.

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

Signed [Signature]
(TECHNICIAN) (DOIC)

FORM CP-2/3
Rev. 9-82

INVOICED
DATE 6-16-83
INV. NO. 4589-W

RECEIVED
STATE CORPORATION COMMISSION
06-13-1983
JUN 13 1983
CONSERVATION DIVISION
Wichita, Kansas