

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20568-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 22-34S-21W
2339 feet from S Section Line, 4790 feet from E Section Line
Lease Name: BARBY-HARPER Well #: 1-22-A
County: CLARK Total Vertical Depth: 5180 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4224		WITH 2 SX CMT
SURF	8.625	855		WITH 700 SX CMT
COND	20	105		WITH 350 SX CMT
PROD	4.5	5174	3000	WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/14/2010 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID B PAULY Company: C.H. TODD Phone: (316) 721-2020

Proposed Plugging Method: SET CIBP @ 4224' WITH 2 SX CMT. PLUG AT 870' WITH 20 SX GEL & 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/14/2010 10:40 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4224' WITH 2 SX CMT. 1ST PLUG AT 870' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 250' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

INVOICED
DATE 4/22/10
INV. NO. 2010010193

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 01

RECEIVED
APR 15 2010
KCC DODGE CITY

Signed Eric MacLaren
RECEIVED (TECHNICIAN)
APR 21 2010
KCC WICHITA

Form CP-218