

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-20519-00-00  
Spot: NWNESW Sec/Twnshp/Rge: 22-34S-21W  
2299 feet from S Section Line, 3767 feet from E Section Line  
Lease Name: BARBY-HARPER Well #: 5-22  
County: CLARK Total Vertical Depth: 5620 feet

Operator License No.: 5055  
Op Name: C. H. TODD, INC.  
Address: 1000 N TYLER STE 100  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4200		WITH 2 SX CMT
SURF	8.625	860		WITH 800 SX CMT
COND	20	80		WITH 800 SX CMT
PROD	4.5	5208	2800	WITH 300 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/31/2010 4:00 PM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: DAVID B. PAULY Company: C.H. TODD Phone: (316) 721-2020

Proposed Plugging Method: CIBP @ 4200' WITH 2 SX CMT. PLUG AT 900' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/31/2010 5:05 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG CIBP @ 4200' & 2 SX CMT. 2ND PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. 3RD PLUG PULL TO 300' & PUMP 40 SX CMT. 4TH PLUG PULL TO 60' & PUMP 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5068	5078		MARMATON
4268	4288		TORONTO

INVOICED

DATE 4/22/10  
INV. NO. 2010010193

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

Steve Durrant  
(TECHNICIAN)

RECEIVED  
APR 12 2010

RECEIVED

APR - 5 2010

KCC DODGE CITY

KCC WICHITA

Form CP-2/3