

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-20816-00-00  
Spot: NENESE Sec/Twnshp/Rge: 22-34S-21W  
2310 feet from S Section Line, 330 feet from E Section Line  
Lease Name: BARBY-HARPER Well #: 7-22-A  
County: CLARK Total Vertical Depth: 5520 feet

Operator License No.: 5055  
Op Name: C. H. TODD, INC.  
Address: 1000 N TYLER STE 100  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5015		WITH 2 SX CMT
SURF	8.625	875		WITH 500 SX CMT
COND	20	78		
PROD	5.5	5488	3000	WITH 400 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/13/2010 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID B. PAULY Company: C.H. TODD Phone: (316) 721-2020

Proposed Plugging Method: CIBP @ 5015' WITH 2 SX CMT. PLUG AT 900' WITH 20 SX GEL & 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/13/2010 1:55 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5015' WITH 2 SX CMT. 1ST PLUG AT 900' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 250' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5083	5093		MARMATON
5065	5075		MARMATION

INVOICED  
DATE 4/22/10  
INV. NO. 2010010193

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 01

RECEIVED  
APR 15 2010  
KCC DODGE CITY

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
APR 21 2010  
KCC WICHITA

Form CP 23