

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20749-00-00
Spot: SENE Sec/Twnshp/Rge: 22-34S-21W
3179 feet from S Section Line, 597 feet from E Section Line
Lease Name: BARBY-HARPER Well #: 12-22
County: CLARK Total Vertical Depth: 5560 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5015		WITH 2 SX CMT
SURF	8.625	848		WITH 500 SX CMT
COND	20	94		
PROD	4.5	5509	3000	WITH 400 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/31/2010 11:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: DAVID B. PAULY Company: C.H. TODD Phone: (316) 721-2020

Proposed Plugging Method: CIBP @ 5015' WITH 2 SX CMT. PLUG AT 870' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/31/2010 12:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG CIBP @ 5015' & 2 SX CMT. 2ND PLUG AT 870' WITH 15 SX GEL & 50 SX CMT. 3RD PLUG PULL TO 300' & PUMP 15 SX CMT. 4TH PLUG PULL TO 60' & PUMP 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5401	5403		MORROW
5065	5073		MARMATON

INVOICED
DATE 4/22/10
INV. NO. 2010010193

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING

Plugged through: TBG

District: 01

RECEIVED

APR - 5 2010

KCC DODGE CITY

Signed

Steve Durrant

(TECHNICIAN) RECEIVED

APR 12 2010

KCC WICHITA