

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19160-00-00
Spot: SENEENE Sec/Twnshp/Rge: 20-21S-5E
4774 feet from S Section Line, 218 feet from E Section Line
Lease Name: STRAIT RANCH Well #: 15
County: MARION Total Vertical Depth: 2292 feet

Operator License No.: 6655
Op Name: CRAWFORD, GARRY F. DBA CRAWFO
Address: PO BOX 727
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	206		100 SX
PROD	5.5	22740		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: BRANCE CRAWFORD Company: _____ Phone: (316) 323-5513

Proposed
Plugging
Method:

AS PER KCC

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2010 12:45 PM KCC Agent: SHANE JONES

Actual Plugging Report:

3/18/10 PHILLIPS WELL SERVICE RIGGED UP ON THE WELL. THEY RAN 2" TUBING TO 2227'. CONSOLIDATED TIED ON AND PUMPED 35 SXS 60/40 POS W/4% GELAND 4.5 % CC. PHILLIPS THEN PULLED ALL BUT 8 JOINTS OF TUBING. CONSOLIDATED RAN ITS WIRE LINE DONE AND TAGGED CEMENT @ 2008'. CONSOLIDATED THEN TIED ON TO THE 2" TUBING AND CIRCULATE WATER UP AND AROUND THE BACKSIDE. THEY CHANGED TO CEMENT AND CIRCULATED 90 SXS. THEY FINISHED AROUND 12:45PM USING A TOTAL OF 125 SXS OF 60/40 POS W/4% GEL TK #23316. 3/22/2010 I CHECKED TOP PLUG FINDING IT HAD FALLEN 140 PLUS FEET. I DUG OUT DOWN TO THE 8 5/8" SURFACE AND ONCE I BROKE THE SEAL AROUND THE SURFACE PIPE. IT TOOK WHAT FLUID WAS AROUND THE BACK SIDE ON A VACUUM. I CALLED BRANCE CRAWFORD AND TOLD HIM MY FINDINGS. THEY WILL NEED TO EITHER GO BACK IN AND PERFORATE AND CIRCULATE CEMENT AGAIN, OR RUN TUBING DOWN THE BACK SIDE AND THE INSIDE OF THE 5.5" AND FILL TO THE SURFACE. 4/5/10 DYNA LOG TAGGED CEMENT @ 141' AND PERFORATED CASING AT 122'. CONSOLIDATED TIED ON AND PUMPED DOWN CASING GOT UP TO A RATE OF 1.5 BBLS @ 300 PSI. THEY PUMPED 35 SXS DOWN CASING NEVER CIRCULATED UP BACKSIDE. WE PUMPED CEMENT DOWN BACKSIDE. THEY USED A TOTAL OF 45 SXS OF 60/40 POS W/4% GEL TK # 23345. TA HAD BEEN APPROVED 6 MONTH IN ACCORDANCE WITH COMPLIANCE AGREEMENT WITH THE DISTRICT 2 OFFICE. WAS ORIGINALLY DENIED DUE TO HIGH FLUID LEVEL POSSIBLE CASING LEAK. SJ

Perfs:

Top	Bot	Thru	Comments
2270	2292	OH	


INVOICED
DATE 4/22/10
INV. NO. 2010010194

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

APR 20 2010 CP-2/3

CONSERVATION DIVISION
WICHITA, KS