

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-115-20763-00-00  
Spot: NENENW Sec/Twnshp/Rge: 28-21S-4E  
5204 feet from S Section Line, 2832 feet from E Section Line  
Lease Name: DEFOREST B Well #: 3  
County: MARION Total Vertical Depth: 2421 feet

Operator License No.: 6131  
Op Name: DRILLERS & PRODUCERS, INC.  
Address: PO BOX 385  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		100 SX
PROD	5.5	2388	323	50 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/31/2010 9:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: BILL ROGERS Company: \_\_\_\_\_ Phone: (620) 382-7212

Proposed  
Plugging  
Method:

AS PER KCC

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: NONE  
Date/Time Plugging Completed: 03/31/2010 2:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

3/31/2010 PHILLIPS WELL SERVICE RAN 2.5" TUBING TO 2377'. CONSOLIDATED TIED ON AND CIRCULATED WATER TO SURFACE. THEY THEN SWITCHED OVER TO CEMENT COMMON W/3% CC AND PUMPED A 35 SX PLUG. PHILLIPS PULED THE TUBING. CONSOLIDATED RAN WIRE LINE DOWN AND TAGGED PLUG @ 2108'. THEY THEN SHOT OFF CASING @ 323', AND PULLED IT OUT. THEY RAN BACK IN WITH 2.5" TO 268'. CONSLIDATED TIED ON AND CIRCULATED CEMENT TO SURFACE. THEY PULLED TUBING AND TOPPED OFF WELL. THEY USED 120 SXS OF 60/40 POS W/4& GEL FINISHING AT 2:00 PM. 4/1/2010 I CHECKED TOP PLUG AND FOUND IT TO BE AT SURFACE OF CASING.

Perfs:


INVOICEL  
DATE 4/22/10  
INV. NO. 2010010197

Remarks: PLUGGED DUE TO 10 YEAR RULE TK # 23358

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 20 2010 Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

TK