

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-115-21233-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 8-22S-4E  
3721 feet from S Section Line, 1207 feet from E Section Line  
Lease Name: SPEIR Well #: 6  
County: MARION Total Vertical Depth: 2410 feet

Operator License No.: 6131  
Op Name: DRILLERS & PRODUCERS, INC.  
Address: PO BOX 385  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211		180 SX
PROD	4.5	2408	1012	50 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/01/2010 9:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: BILL ROGERS Company: \_\_\_\_\_ Phone: (620) 382-7212

Proposed  
Plugging  
Method:

AS PER KCC

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/01/2010 2:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

4/1/2010 PHILLIPS WELL SERVICE RAN 2.5" TUBING TO 2356'. CONSOLIDATED TIED ON AND CIRCULATED WATER TO SURFACE. THEY THEN SWITCHED OVER TO CEMENT COMMON W/4% CC AND PUMPED A 35 SX PLUG. PHILLIPS PULLED THE TUBING. CONSOLIDATED RAN WIRE LINE DOWN AND TAGGED PLUG @ 1935'. THEY THEN SHOT OFF CASING @ 1012' AND PULLED IT OUT. THEY RAN BACK IN WITH 2.5" TO 268'. CONSOLIDATED TIED ON AND CIRCULATED CEMENT TO SURFACE. THEY PULLED TUBING AND TOPPED OFF WELL. THEY USED 110 SXS OF 60/40 POS W/4 & GEL FINISHING AT 2:00 PM. 4/5/2010 I CHECKED TOP PLUG AND FOUND IT TO BE DOWN 8' FROM SURFACE TO CASING. I NOTIFIED BILL ROGERS. THAT THEY WOULD NEED TO TOP OFF THE CASING. BILL SAID THEY WERE ON THEIR WAY TO DUE JUST THAT.

Perfs:

Top	Bot	Thru	Comments
2365	2375	CSG	

INVOICED  
DATE 4/22/10  
INV. NO. 201001097

Remarks: TK #23356

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN) RECEIVED  
KANSAS CORPORATION COMMISSION

APR 20 2010 Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS