

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-30369-00-01
Spot: W2NWNES Sec/Twnshp/Rge: 15-25S-13W
2310 feet from S Section Line, 1220 feet from E Section Line
Lease Name: TEICHMAN Well #: 1
County: STAFFORD Total Vertical Depth: 4340 feet

Operator License No.: 33406
Op Name: GARNER, THOMAS
Address: 305 E 7TH
ST JOHN, KS 67576

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2050		WITH 4 SX CMT
CIBP		2550		
SURF	8.625	300		WITH 250 SX CMT
PROD	4.5	2615	0	WITH 125 SX CM

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/01/2010 10:55 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: THOMAS GARNER Company: _____ Phone: (620) 793-0766

Proposed Plugging Method: SET CIBP @ 2050' & 4 SX CMT. PERFORATE 4 1/2" @ 810'. PUMP DOWN 4 1/2" WITH CMT CIRCULATING UP 8 5/8".

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/01/2010 10:55 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 2050' & 4 SX CMT WITH DUMP BAILER. PERFORATED 4 1/2" @ 810'. PUMPED 180 SX CMT DOWN 4 1/2". HAD CIRCULATION UP 8 5/8" X 4 1/2" ANNULUS BUT LOST IT. 4 1/2" PRESSURED TO 1000 PSIG. PRESSURED 8 5/8" X 4 1/2" TO 300 PSIG WITH 3 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2150	3000		FORT RILEY
2100	2110		FORT RILEY

INVOICED
DATE 4/22/10
INV. NO. 2010010199

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed Richard W. Lacey

RECEIVED
APR - 5 2010

(TECHNICIAN) RECEIVED

APR 12 2010

KCC DODGE CITY

KCC WICHITA

Form CP-273