

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-21052-00-00  
Spot: N2N2NW Sec/Twnshp/Rge: 31-17S-10W  
4945 feet from S Section Line, 3898 feet from E Section Line  
Lease Name: GRIZZELL Well #: 19-31  
County: ELLSWORTH Total Vertical Depth: 3347 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: PO BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3220		
SURF	8.625	325		160 SX
PROD	5.5	3347	2024	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/25/2010 12:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 928-2943

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/25/2010 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 2550' AND CAP WITH 5 SX'S CEMENT. CUT CASING @ 2024' AND PULL TO 1300' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS. PULL CASING TO 950' AND PUMP 35 SX'S CEMENT. PULL CASING TO 375' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF. USED APROX. 160 SX'S CEMENT. TOPPED OFF WITH 15 SX'S ON 4-5-2010.

Perfs:

Top	Bot	Thru	Comments
3255	3333	CSG	ARBUCKLE
2977	3249	CSG	LANSING
2601	2807	CSG	TOPEKA

INVOICED  
DATE 4/22/10  
INV NO. 2010010200

Remarks: 60-40 POZ 4% GEL. QUALITY CEMENT TICKET #3964

Plugged through: CSG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 20 2010

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS