

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23630-00-00
Spot: SESWNENE Sec/Twnshp/Rge: 14-8S-22W
1250 feet from N Section Line, 900 feet from E Section Line
Lease Name: JAMES KEITH Well #: 14-1
County: GRAHAM Total Vertical Depth: 3710 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	255		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/25/2010 6:00 AM
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC
Proposal Rcvd. from: BRAD Company: H&C OIL OPERATING, INC. Phone: (785) 434-7434

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 03/25/2010 7:00 AM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 3642' w/25 sxs.
2nd. Plug at 1680' w/25 sxs.
3rd. Plug at 910' w/100 sxs.
4th. Plug at 305' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:


INVOICED
DATE 4/22/10
INV. NO. 2010010202

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

RECEIVED

CM

APR 12 2010

Form CP-2/3

KCC WICHITA

APR 07 2010