

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21307-00-00
Spot: NW Sec/Twnshp/Rge: 14-34S-25W
1320 feet from N Section Line, 1320 feet from W Section Line
Lease Name: CAUTHERS Well #: 4
County: CLARK Total Vertical Depth: 5750 feet

Operator License No.: 33384
Op Name: HIGH BLUFF OPERATING LLC
Address: 730 17TH ST STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5590		WITH 4 SX CMT
CIBP		5672		
SURF	8.625	711		WITH 400 SX CMT
PROD	4.5	5750	2290	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/05/2010 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RODNEY GONZALES Company: HIGH BLUFF OPERATING Phone: (620) 655-6891

Proposed Plugging Method: SET CIBP AT 5584' WITH 4 SACKS OF CEMENT ON TOP. SET CEMENT PLUG AT 1050' WITH 125 SACKS, NEXT PLUG AT 250' WITH 40 SACKS, NEXT PLUG AT 40' WITH 20 SACKS. 60/40 POS WITH 4% GEL. PER MIKE FROM DODGE CITY OFFICE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2010 11:10 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5590' WITH 4 SX CMT. 1ST PLUG AT 1048' WITH 125 SX CMT. 2ND PLUG AT 244' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5658	5666		
5634	5642		

INVOICED

DATE 4/22/10
INV. NO. 2010010205

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
APR - 7 2010
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
APR 12 2010
KCC WICHITA

Form CP-223