

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22775-00-00
Spot: SWSESE Sec/Twnshp/Rge: 10-30S-14W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: NORRIS Well #: 1-10
County: BARBER Total Vertical Depth: 4805 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4120		
SURF	13.38	249		WITH 275 SX CMT
PROD	4.5	4804	2240	WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2010 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4032' & 4 SX CMT. PLUG AT 800' WITH 15 SX GEL & 50 SX CMT. PLUG AT 280' WITH 100 SX CMT. PLUG AT 40' WITH 45 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/26/2010 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 4022' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 800' WITH 20 SX GEL & 50 SX CMT W/3% CC & 50# HULLS. 2ND PLUG AT 280' WITH 100 SX CMT & 50# HULLS. 3RD PLUG AT 40' WITH 45 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4512	4516		SPF
4238	4246		SPF
4138	4144		SPF
4085	4089		SPF
4072	4079		SPF

INVOICED
DATE 4/22/10
INV. NO. 2010010207

RECEIVED
KANSAS CORPORATION COMMISSION

APR 16 2010

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED

APR - 7 2010

KCC DODGE CITY

Form SP-2/3