

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-05394-00-00  
Spot: SESWSW Sec/Twnshp/Rge: 36-13S-15W  
330 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: DILLNER B Well #: 1  
County: RUSSELL Total Vertical Depth: 3307 feet

Operator License No.: 6296  
Op Name: HOLT, IVAN LEROY  
Address: PO BOX 401  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	301	0	200 SX
PROD	5.5	3307	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/05/2010 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: LEROY HOLT Company: HOLT, IVAN LEROY Phone: (785) 483-2822

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 200# hulls - 10 sxs gel.  
PBSD 3266'. Perf 1600' - 750' - 500'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/05/2010 1:00 PM KCC Agent: RAY DINKEL

**Actual Plugging Report:**

Ran tubing to 2700' - pumped 10 sxs gel - followed with 50 sxs cement with 100# hulls.  
Pulled tubing to 1600' - pumped 100 sxs cement with 100# hulls.  
Pulled tubing to 700' - pumped 80 sxs cement - circulated 10 sxs out.  
POOH. Hooked up to casing and pumped 70 sxs cement. Max. P.S.I. 300#.  
04/07/2010 - checked - filled up 80' down.  
Topped off with 15 sxs cement.  
Branden head and cellar was full of cement.

**Perfs:**

Top	Bot	Thru	Comments
3214	3218		
3139	3141		
3095	3098		
3077	3080		
2954	2958		
2946	2949		
2769	2772		

INVOICED  
DATE 4/22/10  
INV. NO. 2010010208

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 15 2010

Remarks: ALLIED CEMENTING COMPANY-TICKET #41346.

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

CHET LOVING

#1

DILLNER 'B'

36-13-15W  
SE SW SW

Contr.

S & W DRLG

RUSSELL

County

E. 1889RB

Comm.

Comp.

7-19-57

IP

25 BOPD

Tops	Depth	Datum
TOP	2765	-876
TOR	3015	-1126
KG	3055	-1166
ARB	3305	-1416
TD	3307	-1418

Casing

8" 300

5" 3305

CO 3307: SWB 3 BO & 1 BWPB

GORHAM POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS