

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-19153-00-01
Spot: E2NENENE Sec/Twnshp/Rge: 5-8S-24W
4980 feet from S Section Line, 110 feet from E Section Line
Lease Name: TEEL SWD Well #: 1
County: GRAHAM Total Vertical Depth: 1430 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	1430	0	375 SX

Well Type: SWD UIC Docket No: _____ Date/Time to Plug: 03/31/2010 11:00 AM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVE FUNK Company: JASON OIL COMPANY LLC Phone: (785) 324-1041

Proposed Plugging Method:	Ordered 250 sxs 60/40 pozmix - 4% gel - 300# hulls. Tried to wash down with power swivel - drilled to 1440' - could not drill any farther. Decided to plug well.
---------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 03/31/2010 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1440' - pumped 140 sxs cement with 200# hulls.
Pulled tubing out - topped off with 10 sxs cement - full.

Perfs:

INVOICED
DATE 4/22/10
INV. NO. 2010010211

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3787.

Plugged through: TBG

District: 04

Signed *Marvin Mills*
(TECHNICIAN) CM

RECEIVED
KANSAS CORPORATION COMMISSION

APR 19 2010

CONSERVATION DIVISION
WICHITA, KS

APR 14 2010

replacement card

IL COMPANY

5-08 -24W
300'FNL & 110'FEL, NE/4

#308 "D" NANA UNIT

4 E OF MORLAND, KS
NG

cty: GRAHAM
field: NANA NW

API IOG-59757

drig date	11/20/65	drig comp	11/22/65	card issued	03/29/89	last revised	03/29/89
--------------	----------	--------------	----------	----------------	----------	-----------------	----------

.....depth/datum
1000
1145
1330
1430

IP status:

ABD SWDW, SWDW, CHEY SD 1200-1330 ,
INFO RELEASED: 3/29/89 - REISSUED CARD - MAY BE
MISSING FROM SOME FILES
CSG: 7" 1430 / 375 SX
MICT - CO, PF (CHEY SD) 1200-1400, SWDW -
INJECTION RATE SATISFACTORY 11/22/65 (WELL P & A
5/26/88)

IT 1989
 GAS SERVICE, INC.
 KANSAS

Parren.
HHS-2686