

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20734-00-00
Spot: NWNESESW Sec/Twnshp/Rge: 11-29S-41W
1100 feet from S Section Line, 2300 feet from W Section Line
Lease Name: RUBY ARNOLD Well #: 11-2
County: STANTON Total Vertical Depth: 5980 feet

Operator License No.: 33002
Op Name: KERR-MCGEE OIL & GAS ONSHORE LP
Address: PO BOX 1330 REGULATORY GROUP
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5400		WITH 2 SX CMT
SURF	8.625	1649		WITH 700 SX CMT
COND	20	40		3 YARDS
PROD	5.5	5979	1218	WITH 950 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/30/2010 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 5400' WITH 2 SX CMT. PLUG AT 1700' WITH 30 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2010 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5400' WITH 2 SX CMT. FILL HOLE WITH MUD TO 1740'. TAG WITH WIRELINE. 1ST PLUG AT 1740' WITH 25 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5499	5508		W/ 50 SX
5486	5492		W/ 50 SX
5452	5470		OPEN

INVOICED
DATE 4/22/10
INV. NO. 2010010212

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

RECEIVED
APR - 7 2010
KCC DODGE CITY

Signed Ken Jehlik
(TECHNICIAN)

RECEIVED
APR 21 2010
KCC WICHITA