

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04353-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 4-18S-14W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MONROE Well #: 7
County: BARTON Total Vertical Depth: 3528 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3410		
CIBP		3454		
SURF	10.75	953		350 SX
COND	13.38	258		200 SX
PROD	7	3471	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2010 8:00 AM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Rcvd. from: TOM LARSON Company: LARSON OPERATING COMPANY Phone: (620) 793-2168

Proposed Plugging Method: Ordered 760 sxs 60/40 pozmix - 4% gel - 600# hulls - 22 sxs gel.
Perfed 1250' - 925' - 240'. CIBP set in 7" at 3410'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2010 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3260' - tied to tubing and pumped 22 sxs gel - followed with 100 sxs cement with 300# hulls.
Pulled tubing to 1260' - pumped 150 sxs cement with 300# hulls - circulated cement to surface on casing.
Pulled tubing - tied to casing - pumped 35 sxs cement - circulated out surface.
S.I.P. 200#. Shut in. 13 3/8" - full.

Perfs:

Top	Bot	Thru	Comments
3471	3476		ARBUCKLE
3410	3415		LKC 'J'
3298	3300		LKC 'F'
3290	3294		LKC 'E'
3262	3265		LKC 'B'

INVOICED
DATE 4/22/10
INV. NO. 2010010213

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
RECEIVED (TECHNICIAN)
KANSAS CORPORATION COMMISSION

CM

APR 19 2010

Form CP-2/3

APR 14 2010

CONSERVATION DIVISION

CONTINENTAL & PHILLIPS

#7

MONROE

4-18-14W 52
NW SW SE

Contr.

BARTON

County

E 1993

Comm

8-31-50

Comp.

10-27-50

IP

120 BOPD

Tops	Depth	Datum
ANH	946	+1047
LANS	3236	-1243
ARB	3466	-1473
T.D.	3476	-1483

Casing

13" 258
8" 955
5" 3467

1/2 BOPH: ACID 500
SWB 5 BOPH

BOYD POOL

INDEPENDENT OIL & GAS SERVICE