

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-16372-00-00
Spot: E2SWNENW Sec/Twnshp/Rge: 1-16S-14W
990 feet from N Section Line, 1661 feet from W Section Line
Lease Name: SCHNEIDER B Well #: 7
County: BARTON Total Vertical Depth: 3297 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3240		
SURF	10.75	634	0	250 SX
PROD	7	3279	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/09/2010 8:00 AM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Rcvd. from: TOM LARSON Company: LARSON OPERATING COMPANY Phone: (620) 793-2168

Proposed Plugging Method: Ordered 710 sxs 60/40 pozmix - 4% gel - 900# hulls - 21 sxs gel.
Perfed 1680' - 876' - 590'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/09/2010 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3206' - tied to tubing and pumped 21 sxs gel - followed with 100 sxs cement with 300# hulls.
Pulled tubing to 1680' - pumped 240 sxs cement with 300# hulls.
Pulled to 680' - pumped 175 sxs cement with 150# hulls - circulated cement to surface out of casing and surface pipe.
Pulled tubing - topped off with 10 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3279	3297		ARBUCKLE
3192	3196		LKC
3076	3082		LKC

INVOICED
DATE 4/22/10
INV. NO. 2010010213

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3945.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

RECEIVED
KANSAS CORPORATION COMMISSION

APR 19 2010

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

APR 14 2010