

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-16373-00-00  
Spot: W2SENWNW Sec/Twnshp/Rge: 1-16S-14W  
990 feet from N Section Line, 979 feet from W Section Line  
Lease Name: SCHNEIDER B Well #: 8  
County: BARTON Total Vertical Depth: 3312 feet

Operator License No.: 3842  
Op Name: LARSON ENGINEERING, INC. DBA LAR  
Address: 562 W STATE RD 4  
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3300		
SURF	10.75	620	0	225 SX
PROD	7	3289	0	175 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/12/2010 8:00 AM  
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.  
Proposal Rcvd. from: TOM LARSON Company: LARSON OPERATING COMPANY Phone: (620) 793-2168

Proposed Plugging Method: Ordered 710 sxs 60/40 pozmix - 4% gel - 900# hulls - 15 sxs gel.  
Perfed 1700' - 895' - 610'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/12/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3210' - tied to tubing and pumped 15 sxs gel - followed with 100 sxs cement with 300# hulls.  
Pulled tubing to 1690' - pumped 200 sxs cement with 300# hulls.  
Pulled to 680' - pumped 395 sxs cement - circulated cement to surface out of casing and surface pipe.  
Pulled tubing - topped off with 15 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3289	3312		ARBUCKLE OPEN

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

*Bruce Rodie*

(TECHNICIAN)

CM

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 19 2010

APR 14 2010

CONSERVATION DIVISION  
WICHITA, KS