

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22222-00-00
Spot: NWSWSWSE Sec/Twnshp/Rge: 35-18S-29W
602 feet from S Section Line, 2386 feet from E Section Line
Lease Name: SPLITTER Well #: 2-35
County: LANE Total Vertical Depth: 4630 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	265		WITH 175 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/15/2010 3:30 AM
Plug Co. License No.: 33935 Plug Co. Name: H. D. DRILLING, LLC
Proposal Rcvd. from: DOUG ROBERTS Company: H. D. DRILLING, LLC Phone: (785) 372-5419

Proposed Plugging Method: 1ST PLUG AT 2170' WITH 50 SX CMT. 2ND PLUG AT 1320' WITH 80 SX CMT. 3RD PLUG AT 740' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 04/15/2010 5:30 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG AT 2170' WITH 50 SX CMT. 2ND PLUG AT 1320' WITH 80 SX CMT. 3RD PLUG AT 740' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

INVOICED
DATE 4/22/10
INV. NO. 2010010213

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED

APR 16 2010

KCC DODGE CITY

Signed

Steve Durrant

(TECHNICIAN)

RECEIVED

APR 21 2010

KCC WICHITA