

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-30346-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 12-17S-13W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: FINGER Well #: 3  
County: BARTON Total Vertical Depth: 3400 feet

Operator License No.: 5631  
Op Name: LOEWEN OPERATOR, INC.  
Address: 208 S MAIN PO BOX 335  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	232	0	160 SX
PROD	5.5	3396	0	125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/06/2010 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DOUGLAS LOEWEN Company: LOEWEN OPERATOR, INC. Phone: (620) 628-4425

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Old T/A well - emergency plug with rig over the hole.  
Junk in the well at 1230'. Drilled and milled on junk - could not get through.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/06/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Tubing at 980' - pumped 150 sxs cement - circulated to surface.  
Pulled tubing. Tied to backside - pressured to 300# P.S.I. - held.  
Tied to casing - pumped 20 sxs cement - pressured to 300# P.S.I. - shut in.

Perfs:

Top	Bot	Thru	Comments
3210	3213		

INVOICED  
DATE 4/22/10  
INV. NO. 2010010214

Remarks: ALLIED CEMENTING COMPANY-TICKET #36359.

Plugged through: CSG

District: 04

Signed Bruce Rodie

(TECHNICIAN)

CM

RECEIVED

APR 12 2010


Form CP-2/3

KCC WICHITA

APR 08 2010

4-30 Map No.

OPER EARL ALLEN - HOISINGTON, KS.



S-T-R 12-17S-13W  
SPOT SW NW SE  
CO BARTON (KS)  
ELEV 1923 KB

WELL #3 FINGER

CONTR DUKE DRIG. CO.

FIELD FINGER FIELD (LAN)

I.P. P 25 BOPD-NW, LAN 3210-13

(KB SPL)

ANH	808	+1115
HB	3042	-1119
TOR	3060	-1137
DG	3071	-1148
BL	3134	-1211
LAN	3149	-1226
BKC	3208	-1285
CGL	3378	-1455
ARB	3391	-1468
RTD	3400	-1477

SPUD 3-11-66 8" 232 W/160 SX. L.O. CHUBB - GEOL

DST #1 (LAN) 3205-16, OP 40", GTS/40", R 535' OIL, ISIP  
448#/20", FP'S 47-256#, FSIP 438#/20"

RTD 3400, NO LOG, 5½" 3396 W/125 SX.

PF 12/3210-13 (LAN), 500A, § LD - § 10 BO-NW/4 HRS,  
POP, P 25 BOPD-NW, LAN 3210-13 - COMPLETED (4-3-66)

*Data Inc*