

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23398-00-00
Spot: SESW Sec/Twnshp/Rge: 14-9S-20W
780 feet from S Section Line, 1880 feet from W Section Line
Lease Name: LAMBERT Well #: 1
County: ROOKS Total Vertical Depth: 3760 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3650		
SURF	8.625	219	0	w/160 sxs cmt
T1	2.875	3645		
PROD	5.5	3759	0	w/200 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/09/2010 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KENT WILSON Company: MAI OIL OPERATIONS, INC. Phone: (785) 483-1683

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls - 16 sxs gel spacer.
Port collar at 1648' w/400 sxs cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/09/2010 10:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked onto 8 5/8" x 5 1/2" annulus - pumped a barrel and half and pressured up.
Hooked to 5 1/2" casing - pumped 50 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pumped 16 sxs gel spacer - pumped 170 sxs 60/40 pozmix - 4% gel with 200# hulls.
S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3720	3724		
3678	3684		
3671	3675		
3607	3611		
3585	3589		
3572	3578		
3554	3558		
3455	3460		

INVOICED
DATE 4/22/10
INV. NO. 2010010215

RECEIVED
KANSAS CORPORATION COMMISSION

APR 19 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #33902.

Plugged through: CSG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

