

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21502-00-01
Spot: NENE Sec/Twnshp/Rge: 29-30S-18W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: COBB A Well #: 1-29
County: KIOWA Total Vertical Depth: 5100 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3535		
CIBP		5005		
SURF	8.625	727		WITH 290 SX CMT
MSCC		3554		
PROD	4.5	5103	2480	WITH 150 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/31/2010 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVE OLLER Company: MCCOY PETROLEUM Phone: (620) 632-9232

Proposed Plugging Method: SAND TO 3425' WITH 4 SX CMT. PLUG AT 740' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/31/2010 1:45 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 3425' WITH 4 SX CMT. 1ST PLUG AT 740' WITH 15 SX GEL, 50# HULLS, 50 SX CMT WITH 2% CC. 2ND PLUG AT 300' WITH 50# HULLS & 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5016	5024		
4975	4984		
3474	3480		

INVOICED
DATE 4/22/10
INV. NO. 20100102-16

Remarks: USED 60/40 POZMIX 4% GEL QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED
APR - 7 2010
KCC DODGE CITY

Signed

Eric MacLaren

RECEIVED
(TECHNICIAN)

APR 12 2010

KCC WICHITA