

TATE OF KANSAS  
TATE CORPORATION COMMISSION  
30 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RETURN  
K.A.R.-82-3-117

API NUMBER 15 193 20306-0001

LEASE NAME Flipse

WELL NUMBER 3

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1020 Ft. from S Section Line

2100 Ft. from E Section Line

SEC. 24 TWP. 10S RGE. 31W (E) or (W)

COUNTY Thomas

LEASE OPERATOR Swift Energy Company

ADDRESS 16825 Northchase Dr. #400, Houston, TX 77060

PHONE# (281) 874-2507 OPERATORS LICENSE NO. 03269

Date Well Completed 05-12-84

Character of Well SWD

Plugging Commenced 11-24-97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-24-97

The plugging proposal was approved on October 7, 1997 12-16-97 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation N/A Inj well Depth to Top \_\_\_\_\_ Bottom TJD.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	Shale	0	340	8-5/8"	340	Drilling
Anhydrite-Dakota	Clay Shale Sand	0	4327	5-1/2"	4327	Drilling
	Clay Shale Sand					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug are used, state the character of same and depth placed, from feet to feet each set:  
MIRU Poe Well Serv & att to rel pkr. Unscrew safety jt. POOH w/127 jts 2-3/8" seal-tile  
PL tbg (tbg & WH sold to Westlyn Supply Co). RU Allied Cmtg & pmpd 5 1/2" csg full of cmt  
w/50 sx 60-40 poz w/500# cottonwood hulls followed by 250 sx 60-40 poz w/10% gel. Cut-off  
WH 5' below CL & weld plate on top of csg. Well P&A'd on 11-24-97. FINAL REPORT.

Name of Plugging Contractor Allied Cementing Co., Inc. License No. N/A

Address Box 628, Great Bend, KS 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Swift Energy Company

STATE OF Texas COUNTY OF Harris, ss.

Rhonda S. Cook (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed thereon, and the same are true and correct, so help me God.

(Signature) Rhonda S. Cook

(Address) 16825 Northchase Dr. #400



Subscribed AND SWORN TO before me this 10th day of December, 19 97

Betty S. Molter  
Notary Public

My Commission Expires: 9/22/98