

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-193-20279-0000

LEASE NAME Wanda Summers

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 68-25

330 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 25 TWP. 10S RGE. 31 (E) or (W)

LEASE OPERATOR First Energy Corporation

COUNTY THOMAS

ADDRESS 16701 Greenspoint Park Dr. #200

Date Well Completed 11-4-83

PHONE#(713) 875-5755 OPERATORS LICENSE NO. 07506

Character of Well Oil

Plugging Commenced 8-28-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-28-90

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, KS. Carl Goodrow

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Lansing "H" Depth to Top 4116 Bottom 4122 T.D. 4610

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mix & Pump 10 SX 65/35 POZ Mix Cement with 8% gel follow w/50 sx 65/35 POZ mix w/8% gel + 500# cotton seed hulls. Finish filling 4 1/2" csq. to surface w/155 sx 65/35 POZ mix w/8% gel. When cement & hulls started out perfs pressure gradually increased to 1400 psi standing pressure. Displace cement to 6' below ground level. let set over night. install welded cap.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor POE Well Services License No. 3152

Address P.O. Box 115, Oberlin, KS 67749

STATE OF TEXAS COUNTY OF , ss.

Christine Harris (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) Christine Harris


(Address) 16701 Greenspoint Park Dr. #200

SUBSCRIBED AND SWORN TO before me this 11th day of September, 19 90

SEP 13 1990
 9-13-90

Diane Porter
 Notary Public

My Commission Expires:



15-193-20279-0000

WELL LOG


COMPANY FIRST ENERGY CORPORATION
 16701 Greenspoint Park Drive, Suite 200
 Houston, Texas 77060
FARM SUMMERS **NO.** 68-25

SEC. 25 **T.** 10S **R.** 31W
LOC. SE SW SW

RIG. NO. 21
TOTAL DEPTH 4610'
COMM. 9/15/83 **COMP.** 9/27/83

COUNTY Thomas
 KANSAS

CONTRACTOR MURFIN DRILLING COMPANY
 250 North Water, Suite 300
 Wichita, Kansas 67202



CASING
 20 10
 15 8 -5/8" csg set @ 319'w/225 sx Common, 2% gel ELEVATION
 12 6
 13 5
 4-1/2" csg set @ 4609' w/100 sx 50-50 Poz, 2% gel, 10# Gil; PRODUCTION
FIGURES INDICATE BOTTOM OF FORMATIONS
 225 sx D29 w/7 1/2# Gil.

Sand & Soil	175'
Shale (Blue)	320'
Sand & Shale	1995'
Shale	2488'
Anhy.	2521'
Shale	3795'
Lime & Shale	4060'
KC	4110'
Lime & Shale (RTD)	4610'



SEP 13 1990