

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-033-20942-00-00
API NUMBER 15-033-20942

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Miller
WELL NUMBER 6-34
1700 Ft. from N Section Line
2630 Ft. from E Section Line
SEC. 34 TWP. 34S RGE. 20 (E) or (W)
COUNTY Comanche
Date Well Completed 11/24/97
Plugging Commenced 09/27/98
Plugging Completed 10/08/98

LEASE OPERATOR Roberts and Murphy, Inc.
ADDRESS Post Office Box 7125
PHONE# (318) 221-8601 OPERATORS LICENSE NO. 4145

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 3, 1998 (date)
by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Viola Perf 6199-6205 Depth to Top 6151 Bottom 6307 T.D. 6830'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	653	8 5/8	653	0
		0	6515	4 1/2	6515	5355

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Set CIBP @ 6040' and dump bailed 2 sxs cmt on top of CIBP. Cut 4 1/2 csg @ 5355' & pulled out.
Pumped down 8 5/8 csg: 300# Hulls; 10 sxs gel; 50 sxs cmt; 10 sxs gel; 100# Hulls; 150 sxs cmt (60/40 pox mix, 6% gel). Dumped cmt down 8 5/8 from surface to 47 ft.

Name of Plugging Contractor Pratt Well Service License No. 5893

Address Box 847 Pratt, KS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Roberts and Murphy, Inc.

STATE OF Louisiana Parish Caddo COUNTY OF Caddo, ss.

Ken Frazier (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 7125 Shreveport, LA 71137-7125

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 1998

Cindy D. Colquette
Notary Public

My Commission Expires: With Life

CINDY D. COLQUETTE
NOTARY PUBLIC IN AND FOR CADDO PARISH
MY COMMISSION IS FOR LIFE