

15-063-00062-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Gove County. Sec. 26 Twp. 12 Rge. 28 (X) (W)
Location as "NE/CNW/SW" or footage from lines 330' from N line, 600' from
Lease Owner Ben F. Brack Oil Co., Inc. E line of NW/4
Lease Name Graham Well No. 1
Office Address 309 Brown Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 5-8-52 19
Application for plugging filed 5-8-52 19
Application for plugging approved 5-8-52 19
Plugging commenced 5-8-52 19
Plugging completed 5-8-52 19
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes, verbally

Name of Conservation Agent who supervised plugging of this well Eldon Peddy
Producing formation Arbuckle Depth to top 4760 Bottom 4776 Total Depth of Well 4776 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface soil, sand, Gravel & shale	Dry	0	216'	10 3/4"	216'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 195 feet to 40 feet for each plug set.

Gunned pits and filled hole to 195' - drove plug to 195' and cemented through drill pipe with 20 sax cement. Filled hole to 40' - drove plug 40' and cemented with 10 sax to top of surface casing.


RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1952
05-15-1952
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Ben F. Brack Oil Company, Inc.
Address 309 Brown Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Leland E. Brack (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leland E. Brack
309 Brown Bldg., Wichita 2, Kansas
(Address)

Subscribed and sworn to before me this 9th day of May, 1952
Gertrude Crist
Notary Public.



24-2675-5 2-52-20M
PLUGGING
FILE SEC. 2607-11-11
PAGE 15 LINE 16

BEN F. BRACK OIL COMPANY, INC.

GRAHAM #1

330' from W line, 600' from E line
of NW/4 Sec. 26-123-28W

Gove County, Kansas
Commenced: 4-14-52
Completed: 5-8-52

Total Depth: 4776'
Elevation: 2683' DF
2676' Gr.

WELL LOG

Sand - Rock	0 -	41'
Sand & Shale		700
Shale & Shells		1000
Sand		1200
Sand & Shale		1330
Shale		1700
Anhydrite		1710
Shale		1980
Shale & Shells		2650
Lime & Shale		2710
Shale & Lime		2715
Sand & Lime		2756
Shale & Lime		2765
Shale		2910
Lime & Shale		3002
Brown Shale & Sand		3080
Lime & Shale		3195
Shale & Lime		3255
Lime - Cherty		3304
Lime		3332
Shale & Lime		3382
Lime & Shale		3521
Lime		3763
Chalky Lime		3791
Lime		4004
Lime & Shale		4064
Lime		4113
Shale & Lime		4165
Shale		4180
Lime		4191
Lime & Shale		4297
Lime		4307
Lime & Shale		4392
Lime		4444
Shale & Lime		4474
Lime & Sand		4511
Mississippi Lime		4520
Lime		4576
Chert & Lime		4597
Lime		4615
Chert & Lime		4648
Chert		4658
Lime & Chert		4682
Lime		4715
Lime & Chert		4755
Lime		4776

FORMATIONS

Heebner	3845'
Lansing	3875
Conglomerate	4476
Mississippian	4500
Viola	4694
Arbuckle	4740

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1952
05-15-1952
CONSERVATION DIVISION
Topeka, Kansas

216' 10 3/4"

T. D.

D & A

To the best of my knowledge the above is a true and correct statement of all formations and where found.

BEN F. BRACK OIL COMPANY, INC.

Leland E. Brack
Leland E. Brack

PLUGGING

FILE SEC 26-123-28W R 28W
PAGE 15 LINE 16

WITNESSED:

Estelade Crut

May 12, 1952