

15-063-00104-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Gove County. Sec. 23 Twp. 12S Rge. 29W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE SE
Lease Owner Tidewater Oil Company
Lease Name E. M. Bland Well No. 1
Office Address P.O. Box 157, Reece, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed April 9 1964
Application for plugging filed April 9 1964
Application for plugging approved April 9 1964
Plugging commenced April 9 1964
Plugging completed April 9 1964
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4578 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	365'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole w/mud to 600', 1/2
sx hulls, plug 20 sx cement;
mud to 300', 1/2 sx hulls,
plug 20 sx cement; mud to 40',
1/2 sx hulls, 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 16 1964

04-16-1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address Box 173--Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Maxine V. Head (employee of owner) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Head


1720 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of April, 19 64

Jean Hollar

Notary Public.

My commission expires 5-22-66



15-063-00104-00-00

DRILLERS LOG

#1 E.M. Bland

CASING RECORD: 8 5/8" @ 365' w/300 sx cement

COMPANY: Tidewater Oil Company

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: March 26, 1964

COMPLETED: April 9, 1964

TOTAL DEPTH: 4578'

DESCRIPTION: C NE SE
23-12S-29W
Gove Co., Kans.

ELEVATION: 2758 DF
2761 RB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil & Clay & Sand	0	90	
Sand & Shale Streaks	90	315	
Shale	315	365	
Shale & Shells	365	995	
Sand Streaks	995	1020	
Sand & Shale	1020	1700	
Redbed	1700	1769	
Blane Gyp	1769	1791	
Redbed & Shale	1791	2258	
Anhydrite	2258	2299	
Shale	2299	2325	
Shale & Shells	2325	2935	
Shale & Lime	2935	3725	
Lime	3725	4255	
Lime & Shale	4255	4480	
Mississippi	4480	4578	

RECEIVED
STATE CORPORATION COMMISSION

APR 16 1964
04-16-1964
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Head
Maxine V. Head

Subscribed and sworn to before me this 14th day of April, 1964.

Jean Hollan
Notary Public

My Commission Expires:
5-22-66