

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Gove County, Sec. 9 Twp. 12S Rge. XXX 30 (W)

Location as "NE/CNW/SW" or footage from lines C NE SW

Lease Owner Pickrell Drilling Company

Lease Name Hood "A" Well No. 1

Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 11 19 72

Application for plugging filed January 11 19 72

Application for plugging approved January 11 19 72

Plugging commenced January 11 19 72

Plugging completed January 11 19 72

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation Depth to top Bottom Total Depth of Well 4495 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	252'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug @ 1375' w/110 sacks, middle plug @ 275' w/30 sack, top plug @ 40' w/10 sacks.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 18 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
01-18-1972

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss. C. W. Sebitts


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg., Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 14th day of January, 19 72

My commission expires January 19, 1973

Esther Lamone  
Notary Public.



P

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Building  
Wichita, Kansas 67202

Rotary Drilling Commenced 12/27/71

Rotary Drilling Completed 1/14/72

LOCATION: Hood "A" No. 1, C NE SW Sec. 9-12S-30W  
Gove County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: Run 6 jts. 8-5/8" surface casing set @ 252' KB. Cemented  
w/150 sacks. Completed 6:45 P.M. Circulated.

No oil string run. D. & A, Plugged 3:00 P.M. January 11, 1972.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Surface Soil		
255	Shale		C.F.S.
830	Shale - Sand		
1295	Shale w/Sand Streaks	3895	4230
2327	Shale	3910	4325
2365	Anhydrite	3945	4330
2705	Shale	3985	4365
2850	Shale & Lime	4065	4390
2995	Lime & Shale	4093	4405
3180	Shale & Lime	4123	4460
3320	Lime	4145	4485
3810	Lime & Shale	4158	4495
3895	Shale & Lime		
4093	Lime		
4123	Lime & Shale		
4495	Lime, Miss. & RTD		

	S.L.M.
Board	3908.30
Strap	3910.35
	<u>2.05</u> Long

	S.L.M.
	2000
	2500
	3000
	3500
	4000

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 18 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
01-18-1972

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 14th day of January, 19 72, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 19, 1973

Esther Lamone  
Esther Lamone Notary Public

