

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33523
Name: OKT Resources, LLC
Address 1: 1900 East 15th Street
Address 2: Bldg 600
City: Edmond State: OK Zip: 73013 +
Contact Person: David Boyce
Phone: (405) 285-1140

API No. 15 - 077-21540-00-00
If pre 1967, supply original completion date: _____
Spot Description: _____
SE SE SE Sec. 18 Twp. 33 S. R. 8 East West
330 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Harper
Lease Name: Hunt Well #: 1-18

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8 Set at: 284 Cemented with: 175 Sacks
Production Casing Size: 5 1/2 Set at: 4751 Cemented with: 150 Sacks

List (ALL) Perforations and Bridge Plug Sets:

Mississippi @ 4480 - 4492

Elevation: 1332 (G.L. / K.B.) T.D.: 4784 PBTD: 4712 Anhydrite Depth: 1000'
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Set CIBP @ 4400'. Spot 5 sks cmt on CIBP. Set cmt plugs as follows: plug #1 @ 1000' w/50 sks, #2 @ 650' w/50 sks, #3 @ 335' to surface. Plugging orders per Mr. Jeff Klock, April 29, 2010.

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No


If ACO-1 not filed, explain why:

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Robert W. Packard
Address: 2530 NW Willow Road City: Medicine Lodge State: KS Zip: 67104 + 8140
Phone: (620) 886-3431 (620 213-0501 cell)
Plugging Contractor License #: 5105 Name: Clarke Corporation
Address 1: PO Box 187 Address 2: _____
City: Medicine Lodge State: KS Zip: 67104 + 8140
Phone: (620) 886-5665

Proposed Date of Plugging (if known): Estimate May 20th - 25th, 2010 Waiting on Clarke unit.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 4/30/10 Authorized Operator / Agent:  (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 04 2010
KCC WICHITA



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman, Joseph F. Harkins, Commissioner, Ward Loyd, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

OKT RESOURCES, LLC
1900 E 15TH BUILDING 600
EDMOND, OK 73013-6691

May 05, 2010

Re: HUNT #1-18
API 15-077-21540-00-00
18-33S-8W, 330 FSL 330 FEL
HARPER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after November 1, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000