

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 175-20296 - 0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 97/20/76

Well Operator: Herman L. Loeb LLC KCC License #: 3273
(Owner / Company Name) (Operator's)
Address: P O Box 838 City: Lawrenceville
State: IL Zip Code: 62439 Contact Phone: (812) 853 - 3813
Lease: Colburn Well #: 7-63 Sec. 20 Twp. 33 S. R. 32 East West
SW SE SW Spot Location / QQQQ County: Seward

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
1625 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" 24# Set at: 1,639 ft Cemented with: 900 Sacks

Production Casing Size: 4 1/2" 10.5# Set at: 5,752 ft Cemented with: 450 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perforations 5,691-5,697 ft

Elevation: 2661 ft (G.L. / K.B.) T.D.: 5,800 ft PBTD: _____ Anhydrite Depth: 2,650 - 2,915 ft
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Set CIBP @ 5,670 ft, spot 2 sk of cement on plug w/ dump bailer.

Pressure test casing to 500#. If ok, run free-point, shoot csg off at free point. Pump remaining cement plugs as per KCC through casing,

If casing won't test, run tubing to spot plugs. Cut casing off 4 ft below ground level, backfill & smooth location.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? No log available.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Michael Polley

Phone: (719) 342 - 5600

Address: 9223 Lakeview Road City / State: Trinidad, CO 81082

Plugging Contractor: Lasso Energy Service KCC License #: 166945 34391
(Company Name) (Contractor's)

Address: P O Box 925 Woodward, OK 73802 Phone: (620) 482 - 6374

Proposed Date and Hour of Plugging (if known?): Start May 17, 2010 5/14/10

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5/5/10 Authorized Operator / Agent: George A. Bynum
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 10 2010

CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman, Joseph F. Harkins, Commissioner, Ward Loyd, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HERMAN L. LOEB, LLC
PO BOX 838
LAWRENCEVILLE, IL 62439

May 14, 2010

Re: COLBURN #7-63
API 15-175-20296-00-00
20-33S-32W, 330 FSL 1625 FWL
SEWARD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after November 10, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888