

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34004
Name: SAXON OIL COMPANY
Address 1: 5910 N. CENTRAL EXPRESSWAY SUITE 1250
Address 2: _____
City: DALLAS State: TX Zip: 75296 + _____
Contact Person: TED WOOTEN
Phone: (214) 234-0552

API No. 15 - 165-21465 - 0000
If pre 1967, supply original completion date: N/A
Spot Description: _____
N2-S2-SE Sec. 25 Twp. 16 S. R. 20 East West
960 Feet from North South Line of Section
1,320 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: RUSH
Lease Name: HART Well #: 1-25

Handwritten initials and date: 5/12/10

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8" Set at: 289 ft. Cemented with: 170 sx Sacks
Production Casing Size: 5 1/2" Set at: 3856 ft Cemented with: 550 sx Sacks

List (ALL) Perforations and Bridge Plug Sets:

Open hole 3856 - 3859, perms: Pleasanton (3,751' - 3,753') & Kansas City (3,658' - 3,663')

Elevation: _____ (G.L. / K.B.) T.D.: 3,695 PBTD: _____ Anhydrite Depth: 1,460

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____ (Interval)

(Stone Corral Formation)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Set CIBP @ 3,643'; dump 2 sx cement. Run freepoint (stretch) on casing, pull free casing. Spot 80 sk plug @ 950' to cover Permian. Spot 50 sk plug 30ft below surface casing (289'). If can't pull casing call KCC in Great Bend to determine if need to perforate casing and circulate cement.

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

RECEIVED
MAY 17 2010

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

KCC WICHITA

Company Representative authorized to supervise plugging operations: Mark Bieker

Address: P.O. Box 741 City: Hays State: Ks Zip: 67601 + _____

Phone: (785) 621-2721

Plugging Contractor License #: N/A 99996 Name: Allied Cementing

Address 1: 1958 E US Highway 40 Address 2: _____

City: RUSSELL State: KS Zip: 67665 + _____

Phone: (785) 483-2003

Proposed Date of Plugging (if known): MAY 20, 2010

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5/12/10 Authorized Operator / Agent: Ted Wooten (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten signature



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman, Joseph F. Harkins, Commissioner, Ward Loyd, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

SAXON OIL COMPANY
5910 N CENTRAL EXPY STE 1250
DALLAS, TX 75206

May 18, 2010

Re: HART #1-25
API 15-165-21465-00-00
25-16S-20W, 960 FSL 1320 FEL
RUSH COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after November 14, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888