

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
March 2009  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5278  
Name: EOG RESOURCES, INC.  
Address 1: 3817 NW EXPRESSWAY STE 500  
Address 2: \_\_\_\_\_  
City: OKLAHOMA CITY State: OK Zip: 73112 + 1483  
Contact Person: CANDY DRISCOLL  
Phone: (405) 246-3140

API No. 15 - 189-22689-00-00  
If pre 1967, supply original completion date: \_\_\_\_\_  
Spot Description: \_\_\_\_\_  
NW SE NE SW Sec. 9 Twp. 34 S. R. 38  East  West  
1,970 Feet from  North /  South Line of Section  
2,230 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: STEVENS  
Lease Name: EVELYN Well #: 9 #1

Check One:  Oil Well  Gas Well  OG  D&A  Cathodic  Water Supply Well  Other: \_\_\_\_\_  
 SWD Permit #: \_\_\_\_\_  ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8 5/8" Set at: 1621' Cemented with: 300 SKS MIDCON2PP/200 SKS CLASS A Sacks  
Production Casing Size: 4 1/2" Set at: 6792' Cemented with: 230 SKS POZ 50/50 Sacks

List (ALL) Perforations and Bridge Plug Sets:

PERF 6282'-<sup>6301</sup>3601', CIBP @ 6277', PERF 6268-6274'

Elevation: 3252' ( G.L. /  K.B.) T.D.: 6800' PBTD: 6747' EST Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Junk in Hole  Casing Leak at: \_\_\_\_\_  
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

PLUG PER KCC GUIDELINES AND REGULATIONS WHICH MAY INCLUDE: LOAD CSG W/MUD, SET CIBP @ 6218' & CAP W/20' CMT, CUT & PULL FREEPIPE, MIX & SPOT 120 SKS CMT FROM 1674-1235', MIX & SPOT 50 SKS CMT FROM 730-570', TOP OUT W/15 SKS CMT FROM 64-4', DIGOUT/CUT OFF 4' BGL & WELD ON ID PLATE.

Is Well Log attached to this application?  Yes  No Is ACO-1 filed?  Yes  No

If ACO-1 not filed, explain why:

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: LARRY PARTAIN  
Address: 3817 NW EXPRESSWAY STE 500 City: OKLAHOMA CITY State: OK Zip: 73112 + 1483  
Phone: (405) 246-3252  
Plugging Contractor License #: 33338 Name: ORR ENTERPRISES  
Address 1: P.O. BOX 1706 Address 2: \_\_\_\_\_  
City: DUNCAN State: OK Zip: 73534 + \_\_\_\_\_  
Phone: (580) 467-0258

Proposed Date of Plugging (if known): UPON APPROVAL

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 20 2010

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5/19/10 Authorized Operator / Agent: Candy Driscoll  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



**EOG Resources, Inc.**  
3817 NW Expressway  
Suite 500  
Oklahoma City, OK 73112-1483  
(405) 246-3100

May 19, 2010

Kansas Corporation Commission  
Conservation Division  
130 S. Market, Room 2078  
Wichita, Kansas 67202

Re: Form CP-1 (Well Plugging Application Form)

To Whom It May Concern:

Enclosed is Form CP-1 (Well Plugging Application Form) for the following well:

Evelyn 9 #1      9-34S-38W      Stevens County      API 15-189-22689

Please return Notice of Receipt of Well Plugging Application (CP-1) in the envelope provided. If you have questions or require additional information, please call me at (405) 246-3140.

Sincerely,

A handwritten signature in cursive script that reads "Candy Driscoll".

Candy Driscoll  
Operations Assistant

Enclosure

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 20 2010

CONSERVATION DIVISION  
WICHITA, KS

COPY



Mark Parkinson, Governor Thomas E. Wright, Chairman, Joseph F. Harkins, Commissioner, Ward Loyd, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

EOG RESOURCES, INC.  
3817 NW EXPRESSWAY STE 500  
OKLAHOMA CITY, OK 73112-1483

May 24, 2010

Re: Evelyn #9 #1  
API 15-189-22689-00-00  
9-34S-38W, 1970 FSL 2230 FWL  
STEVENS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after November 20, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely

A handwritten signature in cursive script that reads "Steve Bond".

Steve Bond  
Production Department Supervisor