

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19211-00-01
Spot: N2NWSW Sec/Twnshp/Rge: 18-9S-16W
2345 feet from S Section Line, 4377 feet from E Section Line
Lease Name: DOUGHERTY B Well #: 1
County: ROOKS Total Vertical Depth: 3270 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	75	0	w/25 sxs cmt
T1	2.875	3060		
PKR		3060		
PROD	5.5	3166	0	w/100 sxs cmt

Well Type: EOR UIC Docket No: E19206.1 Date/Time to Plug: 05/05/2010 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method:	Ordered out 375 sxs 60/40 pozmix - 4% gel - 700# hulls. No Alt II records. Perf: Salt - Anhy - Base Dakota. Failed MIT. Casing leaks throughout - decided to P/A.	5/10/10 2010061077
---------------------------	---	-----------------------

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 05/05/2010 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes each at 1850' - 1290' - 800'.
Ran tubing to 3141'. Allied pumped 75 sxs neat 60/40 pozmix - 4% gel - followed with 50 sxs cement with 400# hulls.
Pulled tubing to 1898'. Allied pumped 60 sxs cement with 300# hulls.
Pulled tubing to 1280'. Allied pumped 90 sxs cement cwc.
PTOH. Topped off 5 1/2" casing with 15 sxs cement - casing full.
Hooked up to backside and pumped 35 sxs cement.
Max. P.S.I. 150#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3166	3270	OH	LKC Injection

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

RECEIVED

MAY 14 2010

KCC WICHITA

MAY 06 2010