

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-099-20621-00-00  
Spot: SESWSWSE Sec/Twnshp/Rge: 21-34S-20E  
159 feet from S Section Line, 2990 feet from W Section Line  
Lease Name: LINK Well #: 5  
County: LABETTE Total Vertical Depth: 423 feet

Operator License No.: 9386  
Op Name: GUS JONES CABLE TOOL SERVICE, LL  
Address: 149 RD 25  
ELK CITY, KS 67344

Well Type: ST UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/19/2009 8:00 AM  
Plug Co. License No.: 9386 Plug Co. Name: GUS JONES CABLE TOOL SERVICE, LLC  
Proposal Rcvd. from: GUS JONES Company: \_\_\_\_\_ Phone: (620) 332-7637

Proposed Plugging Method: 5 1/2 INCH CASING CEMENTED WITH HIGH TEMPERATURE LUMINITE CEMENT WITH 40 PER CENT SILICA FLOUR. 1 1/2 INCH TUBING WELDED TO OUTSIDE (?) OF CASING FOR THERMOCOUPLE. PERFORATED FROM 342 TO 366 FT WITH 6 SHOTS PER FOOT. FRACTURED WITH 3000 GALLONS PAD, 3000 GALLONS FRAC FLUID WITH 1 LB./GAL 20/40 MESH SAND, 2000 GALLONS FLUSH

Plugging Proposal Received By: RUSSELL HINE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/19/2009 1:30 PM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Ran 3/4" in thermocouple and plugged with 4 sacks. Hooked to 5-1/2" and created a rate of flow and pumped 50 sacks of 60/40 pozmix and shut in at 500psi

Perfs:

RECEIVED  
KCC DISTRICT #3

JUL 9 2009

CHANUTE, KS

RHN

PROCESSED  
5/04/10  
2010010269

RECEIVED  
JUL 13 2009  
KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed

*Russell Hine*

(TECHNICIAN)