

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-199-20241-00-00  
Spot: W2SWNW Sec/Twnshp/Rge: 32-15S-41W  
1830 feet from N Section Line, 200 feet from W Section Line  
Lease Name: KUDER Well #: 3-32  
County: WALLACE Total Vertical Depth: 5175 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	347	0	w/235 sxs cmt
PROD	5.5	5162	0	w/160 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/20/2010 1:00 PM  
Plug Co. License No.: 32997 Plug Co. Name: EASTERN COLORADO WELL SERVICE, LLC  
Proposal Rcvd. from: SHANE PELTON Company: HERMAN L. LOEB, LLC Phone: (618) 943-2227

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 6 sxs CC - 1200# hulls - 30 sxs gel.  
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/21/2010 11:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

8 5/8" surface casing set at 347' w/235 sxs cement.  
5 1/2" production casing set at 5162' w/160 sxs cement.  
Port collar at 1915' w/200 sxs cement.  
TD 5175'. PBTD 5109'. Perforations 5041' - 5047'.  
CIBP set at 5000' with two sxs cement on top.  
Tagged cement at 4980'. Casing holes 2900' - 3300'.  
Ran tubing to 4950' - pumped 15 sxs gel.  
Pulled tubing to 3460' - pumped 10 sxs gel.  
Pulled tubing to 2900' - pumped 5 sxs gel mixed with 250# hulls.  
Pulled tubing to 2750' - pumped 100 sxs cement - 4% CC mixed with 300# hulls.  
Pulled tubing to 1500' - circulated hole clean. Shut down until 8:30 AM 04/21/2010.  
Tagged cement plug at 2560'.  
Pulled tubing to 2530' - pumped 250 sxs cement mixed with 100# hulls.  
Pulled tubing to surface. Topped 5 1/2" casing with 30 sxs cement.  
Connected to 8 5/8" surface casing. Pumped one barrel water and pressured to 500#.

5/04/10  
2010010270

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 30 2010  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #43607 AND #43608.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

APR 22 2010

replacement card

BANKS OIL CO  
WICHITA KS 67202

32-15S-41W  
1830'FNL & 200'FWL, SEC

#3-32 KUDER

site: 10-3/4 S & 2-1/2 E OF WESKAN KS	city: WALLACE	API 15-199-20241
contr: MURFIN DRILLING # 14	field: MOUNT SUNFLOWER SE	
geol: SCOTT BANKS		
fr date 09/06/96	spd date 09/09/96	drig comp 09/17/96
	card issued 01/13/97	last revised 12/08/97


ELV: 3798 KB, 3788 GL LOG	
tops.....	depth/datum
B/ANH.....	2754 + 1044
TOP.....	3936 -138
LANS.....	4196 -398
MARM.....	4508 -710
CHER.....	4714 -916
ATOKA.....	4824 -1026
MRW SH.....	4957 -1159
MRW SD LWR.....	5040 -1242
MRW LM LWR.....	5068 -1270
MISS.....	5144 -1346
RTD.....	5175 -1377
LTD.....	5177 -1379
MRW SD UPR-ABSENT	

**IP status**  
**OIL, P 140 BOPD, NW, MRW 5041-5047, 12/05/96**  
 INFO RELEASED: 12/8/97 - WAS OIL WELL - TIGHT HOLE  
 CSG: 8-5/8" 347 / 235 SX (ALT 2), 5-1/2 5162 / 160 SX, DV  
 TOOL AT 1915 / 200 SX  
 COMMENT: LOST CIRC FROM 3990-3994 (50 BBL)  
 NO CORES  
 DST (1) 4990-5045 (MRW), / 45-45-35-60, GTS/25", NO  
 GAUGE, (2ND OP) FLO OIL, REC 1660' OIL (GR 38)  
 ISIP 648# FSIP 669# IFP 366# -491# FFP 575# -575#  
 TRGT ZN: MRW, PTD 5225 (MISS), MICT - CO, PF  
 (MRW SD LWR) 5041-5047, W / 4 SPF, GSO, NAT, POP,  
 IPP 140 BOPD, NW, 12/5/96

COPYRIGHT 1997  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS