

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01878-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 16-10S-23W  
990 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: DIEBOLDT UNIT Well #: 2-3  
County: GRAHAM Total Vertical Depth: 3821 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	278	0	175 SX
PROD	5.5	3859	0	275 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/26/2010 1:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 567-8104

Proposed Shoot perfs at 260' - 1000' - 1885'.  
Plugging Prior operator left lock set and 24 joints tubing in the hole at 2896'.  
Method: Old squeeze reported at 1254' and 940' with 100 sxs.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/26/2010 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2822' - pumped 250 sxs cement with 600# hulls - good circulation of cement.  
Pulled tubing - tied onto 5 1/2" - squeezed with 90 sxs cement - circulated out the backside.  
Shut in at 200# P.S.I.

Perfs:


Top	Bot	Thru	Comments
3692	3702		LKC F
3682	3687		LKC E
3652	3657		LKC D

Remarks: ALLIED CEMENTING COMPANY-TICKET #41576.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN) RECEIVED  
KANSAS CORPORATION COMMISSION

CM

APR 30 2010 Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

APR 27 2010