

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-00208-00-00  
Spot: N2S2SESE Sec/Twnshp/Rge: 23-33S-31W  
560 feet from S Section Line, 660 feet from E Section Line  
Lease Name: WHEATLEY - A Well #: 3  
County: SEWARD Total Vertical Depth: 6000 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| CIBP   |       | 2670       |             | WITH 3 SX CMT   |
| CIBP   |       | 4840       |             |                 |
| SURF   | 10.75 | 2406       |             | WITH 836 SX CMT |
| PROD   | 7     | 5998       | 2515        | WITH 470 SX CMT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/12/2010 9:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 40 SX CMT. PLUG AT 2430' WITH 200-300# HULLS & 75 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/14/2010 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

STAGE CEMENTING COLLAR @ 2625'. CIBP @ 4840'. CIBP @ 2670' WITH 3 SX CMT.  
1ST PLUG AT 2430' WITH 60 SX CMT. 2ND PLUG AT 1600' WITH 25 SX CMT. 3RD  
PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4896 | 4904 |      | LANSING  |
| 2720 | 2720 |      | WINFIELD |

5/04/10  
2010010274  
RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 30 2010  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

RECEIVED  
APR 19 2010  
KCC DODGE CITY

Signed Ken Jehlik  
(TECHNICIAN)