

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20663-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 21-21S-14W
4328 feet from S Section Line, 1652 feet from E Section Line
Lease Name: TITUS B Well #: 1
County: STAFFORD Total Vertical Depth: 3780 feet

\$ 122.85

Operator License No.: 32422
Op Name: FANSHIER, ROGER
Address: R # 3 BOX 7702
SEWARD, KS 67576

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	280		
PROD	4.5	3779	0	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/26/2010 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 3650' & 2 SX CMT OR RUN TBG TO 3650' & PUMP 50 SX CMT. PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/27/2010 11:15 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

OPERATOR REPORTS THAT HE MADE MANY ATTEMPTS TO RETURN WELL CASING TO SERVICEABLE CONDITION WITHOUT ANY SUCCESS. WELL WAS FLOWING CEDAR HILLS WATER UP 4 1/2". HAD HARD TIME WORKING TBG THROUGH CASING PART @ 680'. WORKED TBG TO 1820' WITH MUCH DIFFICULTY & FINALLY COULD NOT MAKE IT ANY FURTHER. BOTTOM PLUG: WORKED TBG TO 1820' & PUMPED 50 SX CMT. TOP PLUG: PULLED TBG TO 900'. PUMPED 300 SX CMT GOOD CIRCULATION UP 4 1/2" & 8 5/8" & 4 1/2" ANNULUS. RAN OUT OF CMT WITHOUT CIRCULATING CMT TO SURFACE. SDON 4/27/10: FLOW OF WATER HAS STOPPED. TAGGED CMT INSIDE 4 1/2" @ 290' WITH TBG. PUMPED 25 SX CMT DOWN TBG CIRCULATING CMT TO SURFACE UP 4 1/2". PULLED TBG & TOPPED OFF 4 1/2" WITH 2 SX CMT. PRESSURED 8 5/8" X 4 1/2" ANNULUS TO 350 PSIG WITH 90 SX CMT & BLEW HOLE IN 4 1/2".

5/10/10
2010061076

Remarks: USED COMMON CEMENT BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
MAY - 3 2010
KCC DODGE CITY

RECEIVED
MAY 06 2010
KCC WICHITA

Form CP-23