

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22395-00-00

\$ 52.26

Spot: SENSWSW

Sec/Twnshp/Rge: 18-20S-9W

1970 feet from S Section Line,

4392 feet from E Section Line

Lease Name: CHARLENE

Well #: 1-18

County: RICE

Total Vertical Depth: 1608 feet

Operator License No.: 33725

Op Name: FOUNDATION ENERGY MANAGEMEN

Address: 14800 LANDMARK BLVD STE 220
DALLAS, TX 75254

String Size Depth (ft) Pulled (ft) Comments

CIBP 4.5 1490

SURF 8.625 277 190 SX

PROD 4.5 1608 185 SX

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 04/26/2010 11:45 AM

Plug Co. License No.: 32098

Plug Co. Name: CLASSIC WELL SERVICE, INC.

Proposal Rcvd. from: KENT STRUBE

Company: FOUNDATION ENERGY MANAGE

Phone: (620) 786-4161

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 04/26/2010 2:00 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. CIBP ALREADY SET @ 1490'. PERFORATE @ 1250', 850' AND 327'. RUN TUBING TO 1450' AND PUMP 10 SX'S CEMENT. PULL TUBING TO 1250' AND PUMP 35 SX'S. PULL TUBING TO 850' AND PUMP 35 SX'S. PULL TUBING TO 327' AND CIRCULATE CEMENT TO SURFACE. SHUT VALVE ON 5.5" AND CIRCULATE CEMENT OUT OF SURFACE CASING. PULL TUBING OUT AND TOP OFF. USED 345 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
1500	1505	CSG	TOWANDA
1416	1426	CSG	WINFIELD

5/10/10
2010061078

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-36508.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 10 2010

CONSERVATION
WICHITA

✓