

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21870-00-01
Spot: NENENE Sec/Twnshp/Rge: 36-32S-11W
4938 feet from S Section Line, 320 feet from E Section Line
Lease Name: COLEMAN Well #: 2
County: BARBER Total Vertical Depth: 4800 feet

\$ 156. —

Operator License No.: 3288
Op Name: JODY OIL & GAS CORPORATION
Address: PO BOX 422
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	262		WITH 185 SX CMT
PROD	4.5	4616	2040	WITH 225 SX CMT

Well Type: EOR UIC Docket No: E26065.1 Date/Time to Plug: 04/14/2010 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4420' & 4 SX CMT. PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 270' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/14/2010 5:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4420' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 900' WITH 15 SX GEL & 50 SX CMT W/3% CC & 50# HULLS. 2ND PLUG AT 600' WITH 50 SX CMT W/3% CC & 50# HULLS. 3RD PLUG AT 270' WITH 40 SX CMT W/50# HULLS. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4471	4500		

5/10/10
2010061081

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED

APR 22 2010

KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 05 2010

CONSERVATION DIVISION
WICHITA, KS

Form CP-27