

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-05055-00-00 \$ 108,94
Spot: NENE Sec/Twnshp/Rge: 30-20S-5W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: ANTON MATTSON Well #: 3
County: MCPHERSON Total Vertical Depth: 3352 feet

Operator License No.: 31528
Op Name: KELSO, MIKE OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	176		125 SX
PROD	7	3320		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/27/2010 9:45 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE
Date/Time Plugging Completed: 04/27/2010 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM, SAND OPEN HOLE TO 3220' AND CAP WITH 7 SX'S CEMENT. PERFORATE AT 800', 430' AND 250'. RUN TUBING TO 800' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 430' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. USED 245 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3320	3352	OH	

5/10/10
2010061082

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-36510

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 10 2010

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

JK