

\$ 136.66

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-10118-00-01
Spot: NWSWSW Sec/Twnshp/Rge: 9-24S-15W
939 feet from S Section Line, 4922 feet from E Section Line
Lease Name: OCONNOR GAS UNIT Well #: 5-2
County: STAFFORD Total Vertical Depth: 4205 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 1700 N WATERFRONT PKY BLDG 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	230		WITH 185 SX CMT
PROD	5.5	3934	2050	WITH 150 SX CMT

Well Type: EOR UIC Docket No: E22232.1 Date/Time to Plug: 04/29/2010 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3625' & 5 SX CMT. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 260' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/29/2010 12:16 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3620' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 275' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3871	3875		
3794	3798		
3541	3845		

5/10/10
2010061085

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
MAY - 3 2010
KCC DODGE CITY

RECEIVED
MAY 06 2010
KCC WICHITA